Renovation of Squash court

Sr.No.	Description	Unit	Qty	Rate	Amount
1	Removing the existing Wooden Flooring and stacking it within a range of Sqft 680 12.00 8160.00 15 mtrs from the site. Removing the Debri from the site will be in the scope of the client	Sqft			
2	Wooden Flooring			1000 1000	
	"ACTION" -USA MAPLE				
	" 'WSF' , FIBA" & " MFMA " Approved"				
	Providing and installing 20mm - Maple Wooden flooring				
	Application of anti-termite treatment on the floor. Thereon laying of 6 mil HDPE sheet with a overlapping of minimum 6" which acts as a vapiour barrier.	Sqft			

	Thereon fixing of AERO FLOAT 10mm cushion pads at a distance of 350 centre to centre. Thereafter runners of 44mm/45mm x 70mm/71mm at a distance of 350 centre to centre. Finally laying the 20mm Action Maple Solid wooden flooring of 57/83mm width and RL "ACTION FLOOR" Maple Wooden Flooring followed by sanding the wooden flooring and application of MFMA Approved "Poloplaz" "Matt Finish" sports polish which will consist one coat of Sealer and Two Top Coats.		
3	GLASS BACK WALL		
	SFCO Fittings:		200
	Providing and erecting 12mm Toughened, Temepered and Celled Glass Back Wall consisting of 4 panels and 1 door panel supported with 4 verticle fin of 12mm fixed with floor fitting. The glass dimensions shall be 7' X 21'. the glass fitting will be either Aluminium or engineering Plastic Nylone 66 or Acrylic.		

The			
	ne Glass Back Wall will be conformig to WSF requirements		
4 PA	AINTING : (ONLY THE PLAYING AREA)		
Pro	oviding and erecting the scaffolding for the painting work	Sqft	
and	eaning of the wall thoroughly with chemical wash. Thereon application of primer and two top coats with Rebound Paint System (WSF Approved). Painting of all the ree walls i.e. Front Wall & 2 X Side walls.	Sqft	
5 LIN	NE MARKING		
Sq	uash Court Line Marking: Floor in Red PU Enamels	No.	